

JianYan Testing Group Shenzhen Co., Ltd.

Report No.:

CE EMC Test Report

Applicant: Nebra Ltd

Address of Applicant: Unit 4 Bells Yew Green Business Court, Bells Yew Green,

Tunbridge Wells, East Sussex, TN3 9BJ

Equipment Under Test (EUT)

Product Name: Nebra Indoor LoRa Gateway ROCK Pi 4 Version / Nebra Indoor

Helium Hotspot ROCK Pi 4 Version

Model No.: NEBHNT-HHRK4-433, NEBHNT-HHRK4-470, NEBHNT-HHRK4-

868, NEBHNT-HHRK4-915, NEBHNT-HHRK4-433-2, NEBHNT-HHRK4-470-2, NEBHNT-HHRK4-868-2, NEBHNT-HHRK4-915-2, NEBHNT-HHRK4-433-3, NEBHNT-HHRK4-470-3, NEBHNT-HHRK4-868-3, NEBHNT-HHRK4-915-3, NEBHNT-HHRK4-433-3,

NEBHNT-HHRK4-470-3, NEBHNT-HHRK4-868-3, NEBHNT-

HHRK4-915-3

Applicable standards: EN 55032:2015, EN 55035:2017

EN IEC 61000-3-2:2019

EN 61000-3-3:2013+A1:2019

Date of sample receipt: 05 Jan., 2022

Date of Test: 06 Jan., to 24 Jan., 2022

Date of report issue: 25 Jan., 2022

Test Result: PASS

Tested by:	Date:	25 Jan., 2022
Test Engineer	_	
Reviewed by: Project Engineer	Date:	25 Jan., 2022
Approved by: Manager	Date:	25 Jan., 2022

This equipment has been shown to be capable of compliance with the applicable technical standards as indicated in the measurement report and was tested in accordance with the measurement procedures specified in above the application standard version. Test results reported herein relate only to the item(s) tested.

This document cannot be reproduced except in full, without prior written approval of the Company. Any unauthorized alteration, forgery or falsification of the content or appearance of this document is unlawful and offenders may be prosecuted to the fullest extent of the law. Unless otherwise stated the results shown in this test report refer only to the sample(s) tested and such sample(s) are retained for 90 days only.



Version

Version No.	Date	Description
00	25 Jan., 2022	Original





Contents

			Page
1	COV	/ER PAGE	1
2	VER	SION	2
3		ITENTS	
		T SUMMARY	
4	_		
5	GEN	IERAL INFORMATION	5
	5.1	CLIENT INFORMATION	
	5.2	GENERAL DESCRIPTION OF E.U.T.	
	5.3	TEST MODE, TEST VOLTAGE AND TEST ENVIRONMENT	
	5.4	DESCRIPTION OF SUPPORT UNITS	
	5.5	DESCRIPTION OF CABLE USED	
	5.6	MEASUREMENT UNCERTAINTY	
	5.7	ADDITIONS TO, DEVIATIONS, OR EXCLUSIONS FROM THE METHOD	
	5.8 5.9	LABORATORY FACILITY	
	5.9 5.10	MONITORING OF EUT FOR THE IMMUNITY TEST.	
	5.10	TEST INSTRUMENTS LIST	۶
_	_	T RESULTS	
6	IES		
	6.1	EMI (EMISSION)	11
	6.1.1		
	6.1.2		17
	6.1.3		
	6.1.4		
	6.2	EMS (IMMUNITY)	22
	6.2.1		
	6.2.2	311 () 3 ()	
	6.2.3		
	6.2.4		
	6.2.5		
	6.2.6		
	6.2.7	Power frequency magnetic field	34
	6.2.8	3 Voltage dips and interruptions	35
7	TES	T SETUP PHOTO	37
1			
8	EUT	CONSTRUCTIONAL DETAILS	44



4 Test Summary

Test Items	Test Requirement	Test Method	Result
Radiated emission	diated emission EN 55032 EN 55032		PASS
Conducted emission	EN 55032	EN 55032	PASS
Harmonic emission	EN IEC 61000-3-2	EN IEC 61000-3-2	N/A
Flicker emission	EN61000-3-3	EN61000-3-3	N/A
Electrostatic discharges (ESD)	EN 55035	EN61000-4-2:2009	PASS
Continuous RF electromagnetic field disturbances	EN 55035	EN61000-4-3: 2006+A1:2007+A2:201 0	PASS
Electrical fast transients/burst (EFT/B)	EN 55035	EN61000-4-4:2012	PASS
Surges	EN 55035	EN 61000-4-5: 2014+A1:2017	PASS
Continuous induced RF disturbances EN 55035		EN61000-4-6: 2014+AC:2015	PASS
Power frequency magnetic field	EN 55035	EN 61000-4-8:2010	PASS
Voltage dips and interruptions	EN 550 <mark>35</mark>	EN61000-4-11: 2004+A1:2017	PASS

Remark:

- 1. UT is the nominal supply voltage.
- 2. Pass: Meet the requirements.
- 3. N/A: not applicable.



5 General Information

5.1 Client Information

Applicant:	Nebra Ltd
Address:	Unit 4 Bells Yew Green Business Court, Bells Yew Green, Tunbridge Wells, East Sussex, TN3 9BJ
Manufacturer/Factor:	Nebra Ltd
Address:	Unit 4 Bells Yew Green Business Court, Bells Yew Green, Tunbridge Wells, East Sussex, TN3 9BJ

5.2 General Description of E.U.T.

Product name:	Nebra Indoor LoRa Gateway ROCK Pi 4 Version / Nebra Indoor Helium Hotspot ROCK Pi 4 Version					
Model no.:	NEBHNT-HHRK4-433, NEBHNT-HHRK4-470, NEBHNT-HHRK4-868, NEBHNT-HHRK4-915, NEBHNT-HHRK4-433-2, NEBHNT-HHRK4-470-2, NEBHNT-HHRK4-868-2, NEBHNT-HHRK4-915-2, NEBHNT-HHRK4-433-3, NEBHNT-HHRK4-470-3, NEBHNT-HHRK4-868-3, NEBHNT-HHRK4-433-3, NEBHNT-HHRK4-470-3, NEBHNT-HHRK4-470-3, NEBHNT-HHRK4-915-3					
Hardware version:	v1					
Software version:	781099d					
AC adapter:	Model No.:R241-1202500I Input: AC100-240V, 50/60Hz 1.5 A Output: DC 12.0V, 2.5A					
Remark:	Model no.: NEBHNT-HHRK4-433, NEBHNT-HHRK4-470, NEBHNT-HHRK4-868, NEBHNT-HHRK4-915, NEBHNT-HHRK4-433-2, NEBHNT-HHRK4-470-2, NEBHNT-HHRK4-868-2, NEBHNT-HHRK4-915-2, NEBHNT-HHRK4-433-3, NEBHNT-HHRK4-470-3, NEBHNT-HHRK4-868-3, NEBHNT-HHRK4-915-3, NEBHNT-HHRK4-433-3, NEBHNT-HHRK4-430-3, NEBHNT-HHRK4-868-3, NEBHNT-HHRK4-915-3, The difference between the models is that the LoRa Radio module used inside is different for each variant. Along with a respective antenna for each region / frequency. The -2 and -3 flags at the end of the model number relates to the specific chip part number for the main LoRa chip.					



5.3 Test mode, test voltage and test environment

	<u> </u>					
Working:	Keep the EUT in Lanlink mode					
Test voltage:	AC 230V/50Hz					
Remark:	 During the test, pre-scan 110Vac/60Hz and 230Vac/50Hz of the Power supply, found 230Vac/50Hz was worse case mode. The report only reflects the worst mode. 					
Operating Environment:						
Temperature:	Normal: 15°C ~ 35°C, Extreme: -20°C ~ +40°C					
Humidity:	20 % ~ 75 % RH					
Atmospheric Pressure:	1008 mbar					

5.4 Description of Support Units

Manufacturer	Description	Model	S/N	FCC ID/DoC
Lenovo	Laptop	ThinkPad T14 Gen 1	SL10Z47277	DoC

5.5 Description of Cable Used

Cable Type	Description	Length	From	То
N/A	N/A	N/A	N/A	N/A

5.6 Measurement Uncertainty

<u> </u>		
Parameter		Expanded Uncertainty (Confidence of 95%(U = 2Uc(y)))
Conducted Emission for LISN (9kHz ~ 150kHz)		±3.11 dB
Conducted Emission for LISN (150kHz ~ 30MHz)		±2.62 dB
Conducted Emission for ISN (150kHz ~ 30MHz)		±3.54 dB
Radiated Emission (30MHz ~ 1GHz) (3m SAC)		±4.45 dB
Radiated Emission (1GHz ~ 18GHz) (3m SAC)		±5.34 dB
Radiated Emission (30MHz ~ 1GHz) (10m SAC)		±4.32 dB

Note: All the measurement uncertainty value were shown with a coverage k=2 to indicate 95% level of confidence. The measurement data show herein meets or exceeds the CISPR measurement uncertainty values specified in CISPR 16-4-2 and can be compared directly to specified limit to determine compliance.

5.7 Additions to, deviations, or exclusions from the method

No



5.8 Laboratory Facility

The test facility is recognized, certified, or accredited by the following organizations:

• FCC - Designation No.: CN1211

JianYan Testing Group Shenzhen Co., Ltd. has been accredited as a testing laboratory by FCC(Federal Communications Commission). The test firm Registration No. is 727551.

● ISED - CAB identifier.: CN0021

The 3m Semi-anechoic chamber and 10m Semi-anechoic chamber of JianYan Testing Group Shenzhen Co., Ltd. has been Registered by Certification and Engineering Bureau of Industry Canada for radio equipment testing with Registration No.: 10106A-1.

• CNAS - Registration No.: CNAS L15527

JianYan Testing Group Shenzhen Co., Ltd. is accredited to ISO/IEC 17025:2017 General Requirements for the Competence of Testing and Calibration laboratories for the competence of testing. The Registration No. is CNAS L15527.

A2LA - Registration No.: 4346.01

This laboratory is accredited in accordance with the recognized International Standard ISO/IEC 17025:2017 General requirements for the competence of testing and calibration laboratories. The test scope can be found as below link: https://portal.a2la.org/scopepdf/4346-01.pdf

5.9 Laboratory Location

JianYan Testing Group Shenzhen Co., Ltd.

Address: No.101, Building 8, Innovation Wisdom Port, No.155 Hongtian Road, Huangpu Community,

Xinqiao Street, Bao'an District, Shenzhen, Guangdong, People's Republic of China.

Tel: +86-755-23118282, Fax:+86-755-23116366

Email: info-JYTee@lets.com, Website: http://jyt.lets.com

5.10 Monitoring of EUT for the Immunity Test

Visual:	Monitored the LED lighting	of EUT	
Sound:	N/A		
Other:	Monitored the data link of E	UT	



5.11 Test Instruments list

Radiated Emission(3m SAC):							
Test Equipment	Manufacturer	Model No.	Manage No.	Cal.Date	Cal. Due date		
4.4				(mm-dd-yy)	(mm-dd-yy)		
3m SAC	ETS	9m*6m*6m	WXJ001-1	01-19-2021	01-18-2024		
BiConiLog Antenna	Schwarzbeck	VULB9163	WXJ002	03-03-2021	03-02-2022		
Biconical Antenna	Schwarzbeck	VUBA9117	WXJ002-1	06-20-2021	06-19-2022		
Horn Antenna	Schwarzbeck	BBHA9120D	WXJ002-2	03-03-2021	03-02-2022		
Horn Antenna	Schwarzbeck	BBHA9120D	WXJ002-3	06-18-2021	06-17-2022		
Loop Antenna	Schwarzbeck	FMZB 1519 B	WXJ002-4	03-07-2021	03-06-2022		
Pre-amplifier (30MHz ~ 1GHz)	Schwarzbeck	BBV9743B	WXG001-7	03-07-2021	03-06-2022		
Pre-amplifier (1GHz ~ 18GHz)	SKET	LNPA_0118G-50	WXG001-3	03-07-2021	03-06-2022		
Pre-amplifier (18GHz ~ 40GHz)	RF System	TRLA- 180400G45B	WXG001-9	03-07-2021	03-06-2022		
EMI Test Receiver	Rohde & Schwarz	ESRP7	WXJ003-1	03-03-2021	03-02-2022		
Coaxial Cable (30MHz ~ 1GHz)	JYTSZ	JYT3M-1G-NN-8M	WXG001-4	03-07-2021	03-06-2022		
Coaxial Cable (1GHz ~ 18GHz)	JYTSZ	JYT3M-18G-NN- 8M	WXG001-5	03-07-2021	03-06-2022		
Coaxial Cable (9kHz ~ 30MHz)	JYTSZ	JYT3M-1G-BB-5M	WXG001-6	03-07-2021	03-06-2022		
Coaxial Cable (18GHz ~ 40GHz)	JYTSZ	JYT3M-4 <mark>0G</mark> -SS- 8 <mark>M</mark>	WXG001-7	03-07-2021	03-06-2022		
Band Reject Filter Group	Tonscend	JS0806-F	WXJ089 N/A		/A		
Test Software	Tonscend	TS+		Version: 3.0.0.1			

Conducted Emission:					
Test Equipment	Manufacturer	Model No. Manage N		Cal.Date (mm-dd-yy)	Cal. Due date (mm-dd-yy)
EMI Test Receiver	Rohde & Schwarz	ESCI 3	WXJ003	03-03-2021	03-02-2022
RF Switch	TOP PRECISION	RSU0301	WXG003	03-03-2021	03-02-2022
LISN	Schwarzbeck	NSLK 8127	QCJ001-13	03-18-2021	03-17-2022
LISN	Rohde & Schwarz	ESH3-Z5	WXJ005-1	06-18-2021	06-17-2022
ISN	Schwarz <mark>beck</mark>	CAT3 8158	WXJ018	03-03-2021	03-02-2022
ISN	Schwarzbeck	CAT5 8158	WXJ018-1	03-03-2021	03-02-2022
ISN	Schwarzbe <mark>ck</mark>	NTFM 8158	WXJ018-2	03-03-2021	03-02-2022
LISN Coaxial Cable (9kHz ~ 30MHz)	JYTSZ	JYTCE-1G-NN-2M	WXG003-1	03-03-2021	03-02-2022
ISN Coaxial Cable (9kHz ~ 30MHz)	JYTSZ	JYTCE-1G-BN-3M	WXG003-2	03-03-2021	03-02-2022
Test Software	AUDIX	E3	\	ersion: 6.110919/	b



ESD:									
Test Equipment	Manufacturer	Model No.	Manage No.	Cal.Date (mm-dd-yy)	Cal.Due date (mm-dd-yy)				
ESD Simulator	Haefely	ONYX30	WXJ016	03-05-2021	03-04-2022				

Radiated Immunity:	Radiated Immunity:									
Test Equipment	Manufacturer	Model No.	Manage No.	Cal. Date (mm-dd-yy)	Cal. Due date (mm-dd-yy)					
Signal Generator	Rohde & Schwarz	SMB 100B-B106	QCJ005	04-06-2021	04-05-2022					
Solid State Amplifiers	BONN	BLWA 0810- 1000/500D	QCJ005-6	06-21-2021	06-20-2022					
Broadband Amplifier	padband Amplifier Rohde & Schwarz		QCJ005-6	06-21-2021	06-20-2022					
Power Mete	Rohde & Schwarz	NRX	QCJ005-1	04-08-2021	04-07-2022					
Power Sensor	Rohde & Schwarz	NRP6A	QCJ005-2	04-08-2021	04-07-2022					
Power Sensor	Rohde & Schwarz	NRP6A	QCJ005-3	04-08-2021	04-07-2022					
Stacked Log Periodic Antenna Schwarzbeck		STLP 9128E QCJ005-11		N/A	N/A					
Stacked Microwave LogPer. Antenna	Schwarzbeck	STLP 9149	QCJ005-8	N/A	N/A					

Surge \ EFT \ V-dips \ RW	<i>l</i> :				
Test Equipment	Manufacturer	Model No.	Manage No.	Cal.Date (mm-dd-yy)	Cal.Due date (mm-dd-yy)
Four-in-one Immunity test system	EMC PARTNER	IMU-MGE	WXJ079	01-30-2021	01-29-2022
Lightning test system module	EMC PARTNER	EXT-IMU3000S6 (Surge1.2/50us)	WXJ079-4	01-30-2021	01-29-2022
Lightning surge high speed communication line coupling network 8 lines (Surge, RW)	EMC PARTNER	CDN-UTP8 ED3	WXJ079-3	01-30-2021	01-29-2022
Lightning test module of telecommunication terminal	EMC PARTNER	EXT-IMU3000 T6 (Surge 10/700µs)	WXJ079-5	01-30-2021	01-29-2022
Coupling decoupling network of power line (Surge, EFT, RW)	EMC PARTNER	CDN-A-6-32	WXJ079-2	01-30-2021	01-29-2022
EFT test system module	EMC PARTNER	EXT-IMU3000F5	WXJ079-6	01-30-2021	01-29-2022
Capacitive coupling clamp EFT	EMC PARTNER	CN- EFT1000/VERI- CP-EFT	WXJ079-7	01-30-2021	01-29-2022
Voltage dips and Interruption test module	EMC PARTNER	EXT-IMU D	WXJ079-1	01-30-2021	01-29-2022
Ring wave test module	EMC PARTNER	EXT-IMU3000 R6	WXJ079-8	01-30-2021	01-29-2022





Conducted Immunity:										
Test Equipment	Manufacturer	Model No.	Manage No.	Cal. Date (mm-dd-yy)	Cal. Due date (mm-dd-yy)					
Conducted Disturbance Test system	SCHLODER	CDG6000	WXJ017	03-03-2021	03-02-2022					
Coupling/Decoupling Network	SCHLODER	CDN-M2+3	WXJ017-1	03-03-2021	03-02-2022					
EM Clamp	SCHLODER	EMCL-20	WXJ017-2	03-03-2021	03-02-2022					
Coupling/Decoupling Network	SCHLODER	CDN M5-32A	WXJ017-3	02-02-2021	02-01-2022					

PFMF:						
Test Equipment	Test Equipment Manufacturer Model No.				Cal. Due date (mm-dd-yy)	
Power frequency magnetic field generator	Prima	PFM61008TG	WXJ015	03-03-2021	03-02-2022	



6 Test Results

6.1 EMI (Emission)

6.1.1 Radiated emission

6.1.1 Radiated emissi							
Test requirement:	EN 55032						
Test method:	EN 55032						
Test frequency range:	30MHz to 6GHz						
Test distance:	3m						
Receiver setup:	Frequency	Det	ector	RBW	VBW	Remark	
receiver detap.	30MHz-1GHz		si-peak	100kHz	300kHz	QP Value	
	Above 1GHz		eak	1MHz	3MHz	PK Value	
		Ave	erage	1MHz	3MHz	AV Value	
ITE limit:	Frequency		L	imit (dBuV/m @	(3m)	Remark	
	30MHz-230MHz	-		40.0		QP Value	
	230MHz-1GHz			47.0		QP Value	
	1GHz-3GHz	-		50.0 70.0		AV Value PK Value	
	2011- 0011-			54.0		AV Value	
	3GHz-6GHz	Ī		74.0		PK Value	
Test setup:	Below 1GHz:			Above 1G	Hz:		
	Tuntable Osund Reference Plane Optical Cable Feediver Cable Coadal Cable Coadal Cable Tuntable						
	30MHz to 1GHz: 1. The radiated emissions test was conducted in a semi-anechoic chamber. 2. The table top EUT was placed upon a non-metallic table 0.8m above the ground reference plane. And for floor-standing arrangement, the EUT was placed on the horizontal ground reference plane, but separated from metallic contact with the ground reference plane by 0.1m of insulation. 3. Before final measurements of radiated emissions, a pre-scan was performed in the spectrum mode with the peak detector to find out the maximum emissions spectrum plots of the EUT. 4. The frequencies of maximum emission were determined in the final radiated emissions measurement. At each frequency, the EUT was rotated 360°, and the antenna was raised and lowered from 1 to 4 meters in order to determine the maximum disturbance. Measurements were performed for both horizontal and vertical antenna polarization. Above 1GHz: 1. The radiated emissions test was conducted in a fully-anechoic chamber. 2. The table top EUT was placed upon anon-metallic table 0.8m above the						
Test procedure:							






	 ground reference plane. And for floor-standing arrangement, the EUT was placed on the horizontal ground reference plane, but separated from metallic contact with the ground reference plane by 0.1m of insulation. 3. Before final measurements of radiated emissions, a pre-scan was performed in the spectrum mode with the peak detector to find out the maximum emission spectrum plots of the EUT. 4. The frequencies of maximum emission were determined in the final radiated emissions measurement. At each frequency, the EUT was rotated 360°, and the antenna was raised and lowered from 1 to 4 meters in order to determine the maximum disturbance. Measurements were performed for both horizontal and vertical antenna polarization.
Test instruments:	Refer to section 5.11 for details
Test mode:	Refer to section 5.3 for details
Test results:	Passed





Measurement Data:

Product Name:	Nebra Indoor LoRa Gateway ROCK Pi 4 Version / Nebra Indoor Helium Hotspot ROCK Pi 4 Version	Product Model:	NEBHNT-HHRK4-868
Test By:	Mike	Test mode:	Working mode
Test Frequency:	30 MHz ~ 1 GHz	Polarization:	Horizontal
Test Voltage:	AC 230/50Hz		




	NO.	Freq. [MHz]	Reading[d BµV/m]	Level [dBµV/m]	Factor [dB]	Limit [dBµV/m]	Margin [dB]	Trace	Polarity
I	1	53.0375	26.72	12.07	-14,65	40.00	27.93	PK	Horizontal
L	2	87.2300	32.11	14.61	-17.50	40.00	25.39	PK	Horizontal
ľ	3	124.938	37.21	20.46	-16.75	40.00	19.54	PK	Horizontal
	4	249.947	37.60	23.81	-13.79	47.00	23.19	PK	Horizontal
	5	499.965	45.68	38.72	-6.96	47.00	8.28	PK	Horizontal
	6	625.095	41.33	36.02	-5.31	47.00	10.98	PK	Horizontal

Remark:

- 1. Final Level = Receiver Read level + Factor(Antenna Factor + Cable Loss Preamplifier Factor).
- 2. The emission levels of other frequencies are lower than the limit 20dB and not show in test report.



Product Name:	Nebra Indoor LoRa Gateway ROCK Pi 4 Version / Nebra Indoor Helium Hotspot ROCK Pi 4 Version	Product Model:	NEBHNT-HHRK4-868	
Test By:	Mike	Test mode:	Working mode	
Test Frequency:	30 MHz ~ 1 GHz	Polarization:	Vertical	
Test Voltage:	AC 230/50Hz			




	NO.	Freq. [MHz]	Reading[d BµV/m]		evel µV/m]		Factor [dB]		Limit [dBµV/m]		rgin IB]	Trac	ce	Polarity
	1	50.6125	36.91	2	2.21	-14	4.70		40.00	17	.79	PK	(Vertical
4	2	86.0175	43.05	2	5.56	-1	7.49		40.00	14	.44	PK		Vertical
	3	124.938	40.75	2	4.00	-16	3.75		40.00	16	.00	PK	(Vertical
	4	250.068	34.34	2	0.55	-1	3.79		47.00	26	.45	PK		Vertical
	5	499.965	43.95	3	6.99	-6	.96		47.00	10	.01	PK		Vertical
	6	750.103	42.05	3	8.31	-3	.74		47.00	8.	69	PK	(Vertical

Remark:

- 1. Final Level = Receiver Read level + Factor(Antenna Factor + Cable Loss Preamplifier Factor).
- 2. The emission levels of other frequencies are lower than the limit 20dB and not show in test report.



Product Name:	Nebra Indoor LoRa Gateway ROCK Pi 4 Version / Nebra Indoor Helium Hotspot ROCK Pi 4 Version	Product Model:	NEBHNT-HHRK4-433, NEBHNT-HHRK4-470, NEBHNT-HHRK4-868, NEBHNT-HHRK4-915
Test By:	Mike	Test mode:	Working mode
Test Frequency:	1 GHz ~ 6 GHz	Polarization:	Vertical
Test Voltage:	AC 230/50Hz		




NO.	Freq. [MHz]	Reading[d BµV/m]	Level [dBµV/m]	Factor [dB]	Limit [dBµV/m]	Margin [dB]	Trace	Polarity
1	3200.00	52.44	36.51	-15.93	54.00	17.49	AV	Vertical
2	3218.75	58.56	42.69	-15.87	74.00	31.31	PK	Vertical
3	4406.25	57.59	46.43	-11.16	74.00	27.57	PK	Vertical
4	4406.87	49.40	38.25	-11.15	54.00	15.75	AV	Vertical
5	5372.50	56.83	50.70	-6.13	74.00	23.30	PK	Vertical
6	5380.00	48.19	42.12	-6.07	54.00	11.88	AV	Vertical

Remark:

- 1. Final Level =Receiver Read level + Antenna Factor + Cable Loss + Aux Factor Preamplifier Factor.
- 2. The emission levels of other frequencies are lower than the limit 20dB and not show in test report.



Product Name:	Nebra Indoor LoRa Gateway ROCK Pi 4 Version / Nebra Indoor Helium Hotspot ROCK Pi 4 Version	Product Model:	NEBHNT-HHRK4-433, NEBHNT-HHRK4-470, NEBHNT-HHRK4-868, NEBHNT-HHRK4-915
Test By:	Mike	Test mode:	Working mode
Test Frequency:	1 GHz ~ 6 GHz	Polarization:	Horizontal
Test Voltage:	AC 230/50Hz		



NO.	Freq. [MHz]	Reading[d BuV/m]	Level [dBµV/m]	Factor [dB]	Limit [dBµV/m]	Margin [dB]	Trace	Polarity
1	2746.87	50.61	33.04	-17,57	50.00	16.96	AV	Horizontal
2	2803.75	60.15	42.62	-17.53	70.00	27.38	PK	Horizontal
3	3650.62	50.59	35.90	-14.69	54.00	18.10	AV	Horizontal
4	3683.12	58.69	44.14	-14.55	74.00	29.86	PK	Horizontal
5	4543.12	48.72	38.10	-10.62	54.00	15.90	AV	Horizontal
6	4639.37	56.69	46.58	-10.11	74.00	27.42	PK	Horizontal

Remark:

- 1. Final Level = Receiver Read level + Factor(Antenna Factor + Cable Loss Preamplifier Factor_.
- 2. The emission levels of other frequencies are lower than the limit 20dB and not show in test report.




6.1.2 Conducted emission

<u> </u>					
Test Requirement:	EN 55032				
Test Method:	EN 55032				
TestFrequencyRange:	150kHz to 30MHz				
Class / Severity: Class B	Class B				
Receiver setup:	RBW=9kHz, VBW=30kHz				
Limit:	Frequency range (MHz)	Limit	(dBuV)		
		Quasi-peak	Average		
	0.15-0.5	66 to 56*	56 to 46*		
	0.5-5	56	46		
	5-30	60	50		
	* Decreases with the logarithm	of the frequency.			
Test setup:	Refere	nce Plane			
Toot proceedure	AUX Equipment E.U.T Remark E.U.T EMI Receiver Remark E.U.T: Fquipment Under Test LISN Line Impedence Stabilization Network Test table height=0.8m				
Test procedure	The E.U.T and simulators are impedance stabilization network coupling impedance for the material are also connected to the mission of the total are also connected to the mission of the total are checked for material are checked for material are called must be conducted measurement.	ork(L.I.S.N.). Which peasuring equipment. I ain power through a nee with 50ohm termest setup and photogiximum conducted into relative positions o	rovide a 500hm/50uH The peripheral devices LISN that provides a ination. (Please refers graphs). Both sides of erference. In order to f equipment and all of		
Test instruments:	Refer to section 5.11 for detail	S			
Test mode:	Refer to section 5.3 for details				
Test results:	Passed				



Measurement Data:

Product Name:	Nebra Indoor LoRa Gateway ROCK Pi 4 Version / Nebra Indoor Helium Hotspot ROCK Pi 4 Version	Product Model:	NEBHNT-HHRK4-868
Test by:	Mike	Test mode:	Working mode
Test frequency:	150 kHz ~ 30 MHz	Phase:	Line
Test voltage:	AC 230 V/50 Hz		




Freq	Read Level F	LISN actor	Cable Loss	Level	Limit Line	Over Limit	Remark
MHz	dBu∇	₫B	₫B	dBu∀	dBu∀	<u>dB</u>	
1 0.162 2 0.162 3 0.202 4 0.358 5 0.361 6 1.269 7 2.144 8 2.167 9 2.622 10 2.664 11 3.241 12 3.241	32.77 47.94 43.18 36.98 42.51 23.57 33.00 27.08 33.09 26.80 25.78 32.58	0.04 0.04 0.04 0.04 0.06 0.07 0.07 0.08 0.08 0.09	0.01 0.01 0.04 0.02 0.02 0.10 0.18 0.18 0.11 0.07	32.82 47.99 43.26 37.04 42.57 23.73 33.25 27.33 33.28 26.99 25.94 32.74	65.34 63.54 48.78 58.69 46.00 56.00 46.00 46.00	-17. 35 -20. 28 -11. 74 -16. 12 -22. 27 -22. 75 -18. 67 -22. 72 -19. 01	QP Average QP Average QP Average QP Average Average

Notes:

- 1. An initial pre-scan was performed on the line and neutral lines with peak detector.
- 2. Quasi-Peak and Average measurement were performed at the frequencies with maximized peak emission.
- 3. Final Level =Receiver Read level + LISN Factor + Cable Loss + Aux Factor.



Product Name:	Nebra Indoor LoRa Gateway ROCK Pi 4 Version / Nebra Indoor Helium Hotspot ROCK Pi 4 Version	Product Model:	NEBHNT-HHRK4-868
Test by:	Mike	Test mode:	Working mode
Test frequency:	150 kHz ~ 30 MHz	Phase:	Neutral
Test voltage:	AC 230 V/50 Hz		




Freq	Read Level	LISN Factor	Cable Loss	Level	Limit Line	Over Limit	Remark
MHz	₫BuV	dB	₫B	dBu₹	dBu₹	<u>ab</u>	
1 0. 154 2 0. 186 3 0. 226 4 0. 361 5 0. 361 6 2. 110 7 2. 110 8 2. 622 9 2. 650 10 5. 005 11 10. 072 12 10. 397	48. 23 45. 80 32. 22 35. 27 41. 72 30. 05 35. 81 28. 82 35. 70 24. 74 30. 08 37. 41	0.05 0.04 0.04 0.04 0.06 0.06 0.07 0.07 0.10 0.19	0.01 0.02 0.02 0.02 0.02 0.19 0.19 0.11 0.11 0.09 0.13	48. 29 45. 86 32. 28 35. 33 41. 78 30. 30 36. 06 29. 00 35. 88 24. 93 30. 40 37. 72	64.20 52.61 48.69 58.69 46.00 56.00 56.00 50.00	-13.36 -16.91 -15.70 -19.94 -17.00 -20.12 -25.07	QP Average Average QP Average QP Average QP Average QP Average Average

Notes:

- 1. An initial pre-scan was performed on the line and neutral lines with peak detector.
- 2. Quasi-Peak and Average measurement were performed at the frequencies with maximized peak emission.
- 3. Final Level =Receiver Read level + LISN Factor + Cable Loss + Aux Factor.



Product Name:	Nebra Indoor LoRa Gateway ROCK Pi 4 Version / Nebra Indoor Helium Hotspot ROCK Pi 4 Version	Product Model:	NEBHNT-HHRK4-868
Test by:	Mike	Test mode:	Working mode
Test frequency:	150 kHz ~ 30 MHz	Port:	LAN(Cat5)
Test voltage:	AC 230 V/50 Hz		



Freq	Read Level	LISN Factor	Cable Loss	Level	Limit Line		Remark
MHz	₫ĐuV	B	dB	₫₿ū₹	dBu∛	<u>d</u> B	
1 0.358 2 0.377 3 0.918 4 1.088 5 1.552 6 1.577 7 2.066 8 2.567 10 2.622 11 9.861 12 10.019	52.01 45.32 41.11 33.37 41.55 34.78 42.55 36.30 34.49 40.95 31.60 40.20	9, 76 9, 75 9, 55 9, 56 9, 61 9, 62 9, 65 9, 66 9, 66 9, 83 9, 83	0.02 0.03 0.04 0.07 0.15 0.16 0.20 0.20 0.12 0.11 0.13	61, 79 55, 10 50, 70 43, 00 51, 31 44, 56 52, 40 46, 15 44, 27 50, 72 41, 56 50, 16	66. 34 74. 00 64. 00 74. 00 64. 00 64. 00 64. 00 74. 00 64. 00	-23.30 -21.00 -22.69 -19.44 -21.60 -17.85 -19.73 -23.28	Average QP Average QP Average QP Average Average QP Average

Notes:

- 1. An initial pre-scan was performed on the line and neutral lines with peak detector.
- 2. Quasi-Peak and Average measurement were performed at the frequencies with maximized peak emission.
- 3. Final Level =Receiver Read level + LISN Factor + Cable Loss + Aux Factor.




6.1.3 Harmonics Test Result

Test Requirement:	EN IEC 61000-3-2
Test Method:	N/A: See Remark Below
Remark	There is no need for Harmonics test to be performed on this product (rated power is less than 75W) in accordance with EN IEC 61000-3-2. For further details, please refer to Clause 7, Note 1 of EN IEC 61000-3-2 which states: "For the following categories of equipment limits are not specified in this edition of the standard. Note 1: Equipment with a rated power of 75W or less, other than lighting equipment."

6.1.4 Flicker Test Result

Test Requirement:	EN 61000-3-3	
Test Method:	EN 61000-3-3	
Remark:		"Devices and Equipment that do(with the ant voltage fluctuations or flicker need not to






6.2 EMS (Immunity)

6.2.1 Performance Criteria Description in EN 55035

Criterion A:	The equipment shall continue to operate as intended without operator intervention. No degradation of performance or loss of function is allowed below a performance level specified by the manufacturer when the equipment is used as intended. The performance level may be replaced by a permissible loss of performance. If the minimum performance level or the permissible performance loss is not specified by the manufacturer, then either of these may be derived from the product description and documentation, and by what the user may reasonably expect from the equipment if used as intended.
Criterion B:	After the test, the equipment shall continue to operate as intended without operator intervention. No degradation of performance or loss of function is allowed, after the application of the phenomena below a performance level specified by the manufacturer, when the equipment is used as intended. The performance level may be replaced by a permissible loss of performance. During the test, degradation of performance is allowed. However, no change of operating state or stored data is allowed to persist after the test. If the minimum performance level (or the permissible performance loss) is not specified by the manufacturer, then either of these may be derived from the product description and documentation, and by what the user may reasonably expect from the equipment if used as intended.
Criterion C:	Loss of function is allowed, provided the function is self-recoverable, or can be restored by the operation of the controls by the user in accordance with the manufacturer's instructions. Functions, and/or information stored in non-volatile memory, or protected by a battery backup, shall not be lost.





6.2.2 Flectrostatic discharges (FSD)

6.2.2 Electrostatic discharge	jes (ESD)
Test requirement:	EN 55035
Test method:	EN61000-4-2
Discharge voltage:	Contact Discharge, HCP and VCP: ±2kV, ±4kV, Air Discharge: ±2kV, ±4kV, ±8kV
Polarity:	Positive & Negative
Number of discharge:	Contact Discharge: Minimum 25 times at each test point, Air Discharge: Minimum 10 times at each test point.
Discharge mode:	Single Discharge
Discharge period:	1 second minimum
Test setup:	Electrostatic Discharge LUT VCP(0.5m*0.5m) 470K chm Non-Conducted Table 470K chm Ground Reference Plane
Test procedure:	The test was applied on non-conductive surfaces of EUT. The round discharge tip of the discharge electrode was approached as fast as possible to touch the EUT. After each discharge, the discharge electrode was removed from the EUT. The generator was re-triggered for a new single discharge and repeated 10 times for each preselected test point. This procedure was repeated until all the air discharge completed 2) Contact discharge: The test was applied on conductive surfaces of EUT. the generator was re-triggered for a new single discharge and repeated 10 times for each pre-selected test point. the tip of the discharge electrode was touch the EUT before the discharge switch was operated. 3) Indirect discharge for horizontal coupling plane At least 10 single discharges shall be applied at the front edge of each HCP opposite the centre point of each unit of the EUT and 0.1m from the front of the EUT. The long axis of the discharge electrode shall be in the plane of the HCP and perpendicular to its front edge during the discharge. Consideration should be given to exposing all sides of the EUT. 4) Indirect discharge for vertical coupling plane At least 10 single discharges were applied to the center of one vertical edge of the coupling plane. The coupling plane, of dimensions 0.5m X 0.5m, was placed parallel to, and positioned at a distance of 0.1m from the EUT. Discharges were applied to the coupling plane, with this plane in sufficient different positions that the four faces of the EUT are completely illuminated.
Test instruments:	Refer to section 5.11 for details
Test mode:	Refer to section 5.3 for details
Test results:	Passed



Measurement Record:


Test mode:	Working mode					
Tant maluta:	I: Please refer to red arrows as below plots					
Test points:	II:N/A					
Direct discharge						
Discharge Voltage (KV)	Type of discharge	Test points	Observations (Performance Criterion)	Result		
\pm 2, \pm 4	Contact	I	A	Pass		
\pm 2, \pm 4, \pm 8	Air	II	N/A	N/A		
Indirect discharge						
Discharge Voltage (KV)	Type of discharge	Test points	Observation Performance	Result		
± 2, ± 4	HCP-Bottom/Top/ Front/Back/Left/Right	Edge of the HCP	А	Pass		
± 2, ± 4	VCP-Front/Back /Left/Right	Center of the VCP	А	Pass		

Remark:

- A: No degradation in performance of the EUT was observed.
- Red arrow: Air discharge test points.









6.2.3 Continuous RF electromagnetic field disturbances

6.2.3 Continuous RF elec	ctromagnetic field disturbances
Test requirement:	EN 55035
Test method:	EN61000-4-3
Frequency range:	Swept test:80MHz to 1GHz
	Spot test: 1800MHz,2600MHz,3500MHz,5000MHz
Test Level:	3V/m
Modulation:	80%, 1kHz Amplitude Modulation
Performance criterion:	Criteria A
Test setup:	Camera Antenna Tower (Turntable) Ground Reference Plane Generator Generator Amplifier
Test procedure:	 For table-top equipment, the EUT was placed in the chamber on a nonconductive table 0.8m high. For arrangement of floor-standing equipment, the EUT was mounted on a non-conductive support 0.1m above the supporting plane. For human body-mounted equipment, the EUT may be tested in the same manner as table top items. If possible, a minimum of 1 m of cable is exposed to the electromagnetic field. Excess length of cables interconnecting units of the EUT shall be bundled low-inductively in the approximate center of the cable to form a bundle 30 cm to 40 cm in length. The EUT was initially placed with one face coincident with the calibration plane. The EUT face being illuminated was contained within the UFA (Uniform Field Area). The frequency ranges to be considered were swept with the signal modulated and pausing to adjust the RF signal level or to switch oscillators and antennas as necessary. Where the frequency range was swept incrementally, the step size was not exceed 1 % of the preceding frequency value. The dwell time of the amplitude modulated carrier at each frequency was not be less than the time necessary for the EUT to be exercised and to respond, and was not less than 5 s. The test normally was performed with the generating antenna facing each side of the EUT. The polarization of the field generated by each antenna necessitates testing each selected side twice, once with the antenna positioned vertically and again with the antenna positioned horizontally. The EUT was performed in a configuration to actual installation conditions, a video camera and/or a audio monitor were used to monitor the performance of the EUT.
Test instruments:	Refer to section 5.11 for details
Test mode:	Refer to section 5.3 for details
Test results:	Passed



Measurement Record:

Test mode: Working mode

Continuous RF electromagnetic radiated field disturbances swept test

Frequency	Level	Modulation	Antenna Polarization	EUT Face	Observations (Performance Criterion)	Result
		V		А	Pass	
			Н	Front	А	Pass
			V	6	А	Pass
	1 kHz,	Н	Rear	А	Pass	
		V	1 - 4	A	Pass	
00 MH= 4 CH=	2 1//	80 % Amp. Mod, 1 % increment, dwell time=5seconds	Н	Left	A	Pass
80 MHz-1 GHz	3 V/M		V	Diaht	Α	Pass
			Н	Right	Α	Pass
			V	_	А	Pass
			Н	Тор	Α	Pass
			V	Dettern	А	Pass
			Н	Bottom	А	Pass

Remarks:

A: No degradation in the performance of the E.U.T. was observed.

Continuous RF electromagnetic radiated field disturbances spot test

Frequency (+/-1%)	Level	Modulation	Ante <mark>nn</mark> a Polar <mark>iza</mark> tion	EUT Face	Observations (Performance Criterion)	Result		
			V	Front	A	Pass		
			Н	FIONI	Α	Pass		
			V	Deer	Α	Pass		
1800MHz,	1 kHz,	Н	Rear	Α	Pass			
		V		Α	Pass			
2600MHz,	3500MHz, 3500MHz, 5000MHz	dwell	Н	H	Α	Pass		
3500MHz,			V		V	Dialet	Α	Pass
5000MHz				Right	Α	Pass		
	ume=bseconds		Т	Α	Pass			
			Тор	А	Pass			
		V	Dettern	Α	Pass			
			Н	Bottom	Α	Pass		

Remarks:

A: No degradation in the performance of the E.U.T. was observed.



6.2.4 Electrical fast transients/burst (EFT/B)

Test requirement:	EN 55035
Test method:	EN61000-4-4
Test level:	1.0kV on AC port 0.5kV on Lan port
Polarity:	Positive & Negative
Repetition frequency:	5kHz
Burst duration:	15ms
Burst period:	300ms
Test duration:	2 minute per level & polarity
Performance criterion:	В
Test setup:	Bull Non-conducted table Ground Reference Plane Ground Reference Plane
Test procedure:	The EUT and its simulators were placed on the ground reference plane and were insulated from it by a wood support 0.1m + 0.01m thick. The ground reference plane was 1m*1m metallic sheet with 0.65mm minimum thickness. This reference ground plane was project beyond the EUT by at least 0.1m on all sides and the minimum distance between EUT and all other conductive structure, except the ground plane was more than 0.5m. All cables to the EUT was placed on the wood support, cables not subject to EFT/B was routed as far as possible from the cable under test to minimize the coupling between the cables. Test on Signal Ports, Telecommunication Ports and Control Ports: The EFT interference signal is through a coupling clamp device couples to the signal and control lines of the EUT with burst noise for 2 minutes. Test on power supply ports: The EUT is connected to the power mains through a coupling device that directly couples the EFT/B interference signal. Each of the Line and Neutral conductors is impressed with burst noise for 2 minutes. The length of the signal and power lines between the coupling device and the EUT is 0.5m
Test instruments:	Refer to section 5.11 for details
Test mode:	Refer to section 5.3 for details
Test results:	Passed




Measurement Record:

Test mode: Working mode

Lead under Test	Level (±kV)	Coupling Direct/Clamp	Observations (Performance Criterion)	Result
L	± 1.0	Direct	A	Pass
N	± 1.0	Direct	A	Pass
L-N	± 1.0	Direct	А	Pass
Lan	± 0.5	Clamp	A	Pass

Remark:

A: No degradation in the performance of the E.U.T. was observed.





6.2.5 Surges

Test requirement:	EN 55035		
•			
Test method:	EN61000-4-5		
Test level:	± 1 kV Live to Neutral: Differential mode		
	± 2 kV Live to Earth or Neutral to Earth: Common mode		
	± 0.5 kV For Lan Port		
Polarity:	Positive & Negative		
Generator source impedance:	2Ω (line-line coupling)		
Test interval:	60s between each surge		
No. of surges:	5 positive, 5 negative at 0°, 9 <mark>0°,</mark> 180°, 270°.		
Performance criterion:	В		
	Non-conducted table Ground Reference Plane Ground Reference Plane		
Test procedure:	 For line-to-line coupling mode, provide a 1kV 1.2/50us voltage surge (at open-circuit condition) and 8/20us current surge to EUT selected points, and for active line / neutral lines to ground are same except test level is 2kV. At least 5 positive and 5 negative (polarity) tests with a maximum 1/minrepetition rate are applied during test. Different phase angles are done individually. Record the EUT operating situation during compliance test and decide the EUTimmunity criterion for above each test. 		
Test instruments:	Refer to section 5.11 for details		
Test mode:	Refer to section 5.3 for details		
Test results:	Passed		



Measurement Record:

Test mode: Working mode

Location	Level(kV)	Pulse No	Surge Interval	Phase(deg)	Observations (Performance Criterion)	Result					
			00-	0°	Α	Pass					
	_			90°	Α	Pass					
L-IN	L-N ±1 5]		5	5 6]		60s	180°	А	Pass
				270°	A	Pass					
Lan	± 0.5	5	60s		A	Pass					

Remark:

A: During the test, The EUT works normal, and after the test, the function of the EUT is normal.



6.2.6 Continuous induced RF disturbances

Test requirement: EN 55035		
Test method: EN61000-	EN61000-4-6	
Frequency range: 0.15MHz to	0.15MHz to 80MHz	
Test level: 0.15-10MH 10-30MHz 30-80MHz Audio outp	:3-1V	
Modulation: 80%, 1kHz	z Amplitude Modulation	
Performance criterion: Criteria A		
Signal	Generator Power Amplifier Fixed Pad CND EUT Insulating Support 10cm Ground Reference Plane Ground Reference Plane	
2) The E ground placed CDN a ground possib 3) The di CDN. 4) The E climati 5) The fr signal modul. 6) The rafreque the sta	UT are placed on an insulating support 0.1m high above a dreference plane. CDN (coupling and decoupling device) is on the ground plane about 0.3m from EUT. Cables between and EUT are asshort as possible, and their height above the difference plane shall be between 30 and 50 mm (where le). Isturbance signal described below is injected to EUT through a sturbance signal described below is injected to EUT through a sturbance signal described below is injected to EUT through a sturbance signal described below is injected to EUT through a sturbance signal mode and sturbance signal some amplitude and with the disturbance signal some amplitude and with a 1 kHz sinewave. The sturbance is sweet from 0.150MHz to 80MHz using 3V level, and with the disturbance signal 80% amplitude and with a 1 kHz sinewave. The sturbance is sweet from 0.150MHz to 80MHz using 3V level, and with the disturbance signal 80% amplitude and with a 1 kHz sinewave. The sturbance is sweet from 0.150MHz to 80MHz using 3V level, and with the disturbance signal 80% amplitude and with a 1 kHz sinewave. The sturbance is sweet from 0.150MHz to 80MHz using 3V level, and with a 1 kHz sinewave. The sturbance is sweet from 0.150MHz to 80MHz using 3V level, and with a 1 kHz sinewave. The sturbance is sweet from 0.150MHz to 80MHz using 3V level, and with a 1 kHz sinewave. The sturbance is sweet from 0.150MHz to 80MHz using 3V level, and with a 1 kHz sinewave is sweet from 0.150MHz to 80MHz using 3V level, and the sturbance is sweet from 0.150MHz to 80MHz using 3V level, and the sturbance is sweet from 0.150MHz to 80MHz using 3V level, and the sturbance is sweet from 0.150MHz to 80MHz using 3V level, and the sturbance is sweet from 0.150MHz to 80MHz using 3V level, and the sturbance is sweet from 0.150MHz to 80MHz using 3V level, and the sturbance is sweet from 0.150MHz to 80MHz using 3V level, and the sturbance is sweet from 0.150MHz to 80MHz using 3V level, and the sturbance is sweet from 0.150MHz to 80MHz using 3V level, and the sturbance is sweet from	
Test instruments: Refer to se	ection 5.11 for details	
Test mode: Refer to se	ection 5.3 for details	
Test results: Passed		



Measurement Record:

Test mode: Working mode

Frequency	Injected Position	Test Level	Modulation	Step Size	Dwell Time	Observations (Performance Criterion)	Result
150kHz to 10MHz	AC Main Lan Port	3V	80%, 1kHz - Amp. Mod.	1%	2s	Α	Pass
10MHz to 30MHz		3V to1V				А	Pass
30MHz to 80MHz		1V				А	Pass

Remark:

A: No loss of function was observed.





6.2.7 Power frequency magnetic field

Test requirement:	EN 55035
Test method:	EN61000-4-8
Test frequency:	50/60 Hz
Test level:	1 A/m
Performance criterion:	Criteria A
Test setup:	Twisted cable length maximum 2 m
Test procedure:	The EUT place center of the test magnetic field coils. The plane of the inductive coil shall then be rotated by 90° in order to expose the EUT to the test field with different orientations. The signal generator generates a magnetic field of 1A/m for testing.
Test instruments:	Refer to section 5.11 for details
Test mode:	Refer to section 5.3 for details
Test results:	Passed

Measurement Record:

Test mode: Working mode

	Test Frequency (Hz)		Test Level (A/m)	Observations (Performance Criterion)	Result
	50		1	А	Pass
	60		1	А	Pass
Remark: A: No loss of function was observed.					



6.2.8 Voltage dips and interruptions

6.2.6 Voltage dips and in	terr aptions					
Test requirement:	EN 55035					
Test method:	EN61000-4-11					
Test level:	0% of VT(Supply Voltage) for 0.5 period 70% of VT(Supply Voltage) for 25 period 0% of VT(Supply Voltage) for 250 period					
No. of dips / Interruptions:	3 per Level					
Performance criterion:	>95% VD, 0.5 periodPerformance criterion: B 30% VD, 25 periodPerformance criterion: C >95% VI, 250 periodPerformance criterion: C					
Test setup:	EMC Tester But Non-conducted table Ground Reference Plane Ground Reference Plane					
Test procedure:	 The EUT and test generator were setup as shown on above setup photo. The interruptions are introduced at selected phase angles with specified duration. Record any degradation of performance. 					
Test instruments:	Refer to section 5.11 for details					
Test mode:	Refer to section 5.3 for details					
Test results:	Passed					



Measurement Record:

Test mode: Working mode

Test Level % U _T	Duration (Periods)	Phase angle		Time between dropout	Observations (Performance Criterion)	Result			
Test voltage: AC 230V/50Hz									
0	0.5	0°, 90°, 180°, 270°	3	10ms	А	Pass			
70	25	0°, 90°, 180°, 270°	3	500ms	А	Pass			
0	250	0°, 90°, 180°, 270°	3	5000ms	В	Pass			
Test voltage: AC 110V/60Hz									
0	0.5	0°, 90°, 180°, 270°	3	10ms	А	Pass			
70	30	0°, 90°, 180°, 270°	3	500ms	A	Pass			
0	300	0°, 90°, 180°, 270°	3	5000ms	В	Pass			


Remark:


A: No loss of function was observed.

B:After the test, the equipment can operate as intended without operator intervention. No loss of function was observed.




Test Setup Photo













Conducted Emission (LAN Port)



































8 **EUT Constructional Details**

Reference to the test report No..

